

## DEMOLITION NOTES

- THE DEMOLITION CONTRACTOR SHALL COMPLY WITH THE FLORIDA BUILDING CODE CHAPTER 33 AND ALL OTHER APPLICABLE LOCAL, STATE OR FEDERAL REGULATIONS.
- 2. THE OWNER SHALL NOT AUTHORIZE ANY IMPROVEMENT OR DEMOLITION WORK UNTIL PERMIT IS SECURED FROM ALL THE
- AGENCIES HAVING JURISDICTION.


  3. CONTRACTOR SHALL VERIFY WITH ALL UTILITIES COMPANIES (GAS, ELECTRICITY, PHONE, CABLE, WATER AND SEWER, ETC.) AND STAKE OUT IN THE FIELD ALL UNDERGROUND UTILITIES KNOWN OR ENCOUNTERED BEFORE PROCEEDING WITH THE EXCAVATION WORK.
- 4. THE ARCHITECT/ENGINEER SHALL CHECK ANY DEMOLITION AND/OR REMOVAL OF STRUCTURAL MEMBERS REQUIRED BY THESE DOCUMENTS BEFORE ACTUAL REMOVAL. ANY ADDITIONAL DOCUMENTATION NECESSARY BECAUSE OF CONCEALED CONDITIONS SHALL BE PREPARED AND APPROVED BEFORE CONTINUATION OF DEMOLITION ACTIVITIES.
- REMOVE ALL INTERIOR FINISHES INCLUDING PANELING, CERAMIC TILES, AND FLOORING AND DROPPED CEILINGS AS REQUIRED BY THE CONSTRUCTION DOCUMENTS PLANS.
- 6. REMOVE ALL EXISTING ELECTRICAL DEVICES, LIGHTING, CONDUIT, ETC., THROUGHOUT IN AREAS TO BE DEMOLISHED INDICATED IN THE PLAN.
- 7. REMOVE EXISTING NON-USABLE HEATING, VENTILATION AND AIR CONDITIONING EQUIPMENT AND DUCTWORK ON THE INTERIOR AND
- EXTERIOR OF THE AREAS TO BE DEMOLISHED.

  8. REMOVE AND PERMANENTLY CAP ALL PLUMBING LINES ON THE
- INTERIOR AND EXTERIOR OF THE AREAS TO BE DEMOLISHED.

  8. COORDINATE ALL DEMOLITION ACTIVITIES WITH THE PHASED NEW CONSTRUCTION AS INDICATED IN THE CONSTRUCTION DOCUMENTS.
- REMOVE ANY ROTTEN WOOD, OXIDIZED METAL OR SPILLED CONCRETE THAT MAY BE FOUND. REPLACE AS DIRECTED OR AS REQUIRED.
- PHASE DEMOLITION ACTIVITIES TO MAINTAIN THE "DRY-IN" CONDITION OF THE BUILDING INTERIOR.
- 11. MAINTAIN FIRE ENVELOPE INTEGRITY AT ALL TIMES DURING
  DEMOLITION OPERATIONS.
- MAINTAIN CLEAR ACCESS TO AND LIGHTING OF ALL THE REQUIRED MEANS OF EGRESS. MAINTAIN EXISTING STANDPIPES AND SPRINKLER SYSTEM IN WORKING CONDITION.
- 13. MAINTAIN NOT LESS THAN SIX 2A:10B:C FIRE EXTINGUISHERS LOCATED TO COMPLY WITH NFPA 10.
   14. SALVAGE ELEMENTS THAT ARE SCHEDULED TO BE RE-INSTAL
- SALVAGE ELEMENTS THAT ARE SCHEDULED TO BE RE-INSTALLED; ALL OTHER DEBRIS SHALL BE REMOVED FROM THE PREMISES AND DISPOSED OF IN STRICT ACCORDANCE WITH ALL APPLICABLE REGULATIONS.

Miami Dade County Department of Regulatory And Economic Resources 0001149691 - 6/28/2016 7:02:10 AM D-1-06202016.pdf

ExaminerDate Time StampDisp.TradeStamp NameJoAnn Pirrello6/22/2016 10:04:40 AMAZONEPartial DemoHoushang Khabari 6/23/2016 6:23:15 PMABLDGDemolitionRogelio Lorenzo6/22/2016 11:56:08 AMAPLUMDemolitionJeanne Clarke6/22/2016 11:54:37 AMASTRUDemolition





Design Group, LLC
AA26001282
370 MIRACLE MILE
CORAL GABLES, Florida 33134
Tel. 305.444.5545
Fax. 305.444.5509
www.dnbdesigngroup.com

## ALVAREZ RESIDENCE

10245 SW 141ST CT. MIAMI, FLORIDA

## MARCOS ALVAREZ 10245 SW 141ST CT

786.547.7109

DNB PROJECT NUMBER

OWNER'S PROJECT NUMBER

ISSUED FOR:
BUILDING PERMIT

TYPE OF DOCS:

## CONSTRUCTION DOCUMENTS

No.	DATE	REVISION	BY
			· · · · · · · · · · · · · · · · · · ·

DRAWN BY:	APPROVED BY:	
A.C.	F.D.	
DATE:	SCALE:	
02.05.16	AS SHOWN	

CONSULTANTS:



FRANCILIS J. DOMOND, R.A. AR - 93304

This drawing is the property of DNB Design Group and is not to be reproduced or copied in whole or part. It is not to be used on any other project and is to be returned on

COPYRIGHT © 2013

SHEET TITLE

DEMOLITION FLOOR PLAN

SHEET NUMBER

D-1